



RFQ 23-001 BASEBALL Infield TURF

ADDENDUM #2

ISSUED FEBRUARY 28, 2023

1. Are the bullpens included in the “infield” area to be replaced?

Yes. The base bid section 2.2 Services section F is hereby amended:

Construction/ installation of the new baseball artificial turf for the infield only including the bullpens and subsurface improvements required by the turf manufacturer (approximately 53,000 square feet, which includes the bullpens. Color to be selected by owner. Allowance synthetic turf manufacturers are as follows: Astroturf, FieldTurf, Helas Turf, Shaw Sports Turf, Sports Turf, Ram Turf, and Mondo Turf. No other manufacturers will be substituted. Information should be provided as to where the materials are sourced and turf is manufactured.

2. Does the college want the curb by the fence line removed if the warning track option is approved, optional bid #1?

No the curb does not need to be demolished and removed adjacent to the fence line. The curb between the warning track and the grass would be removed and replaced. Bidders should provide pricing to replace the curb to nail board versus replacement curbing made from synthetic wood materials.

3. Where does the current field drain to?

The turf drains towards the south and east of the current field.

4. Are there drainage issues with the current synthetic turf infield?

No. There are drainage areas in the outfield where water ponds, but not in the infield turf area. Attached is a topographical map of the field.

5. Where will the three logos be placed and what size?

The college logo would be replaced in the current location centered behind home plate with the same dimensions. This center logo is approximately 20 ft. x 14 ft.

Two additional logos with the college mascot the Blue Devil would be placed on either side of the main logo. These logos would be approximately 4 ft in diameter.

Map: Topographical Map



